

technical specifications



# **Technical Specifications**

Our dedicated team of in-house technicians ensures precision and reliability in every aspect of audio-visual production.

#### Services

We offer a full range of audio-visual production including: Live streaming and online presentations Speaker audio and panel sessions Professional, seamless conference presentations Band production and lighting packages

#### **Tailored Solutions**

No two events are the same. We work closely with you to understand your unique requirements and tailor our services to meet your specific needs.

paranaple convention centre

Phone: (03) 6420 2950

paranapleconventioncentre.com.au

**Operations Coordinator** 

Matt Groom

Mobile: 0417 341 377

Email: mgroom@devonport.tas.gov.au

Administration & Venue Bookings

Phone: (03) 6420 2950

Email: functions@devonport.tas.gov.au



# **Venue Capacity**

Total: 800 (Theatre Seating) 400 (Banquet)

#### **Technical Staff**

The paranaple convention centre utilise a Tech on Duty system, who must be present at all times whilst the convention centre is in use for which hirers will be charged at the current rate.

The convention centre provides professional FOH & Technical staff at cost to Hirer.

Please contact convention centre management for all Hire Fees.

# Staging Area

The paranaple convention centre has a modular pro-stage scalable stage available at cost to hirers. It consists of 16 1m X 2m panels with stairs, skirts, side rails and wheelchair accessible ramp if required. It can be set in any preferred configuration at heights of 300mm, 600mm or 900mm. Additional panels are available.

# **Loading Bay Access**

A covered loading bay is situated on the western side of the building with access from Best Street. The Loading bay is restricted to a 15 minute time period. Loading is via a goods lift rated at 4 tonnes. Contact your functions officer to book bump in / out times.

#### **Disabled Access**

All parts of the paranaple convention centre has unfettered access, including stages if requested.

# **Electrical Safety**

Testing and Tagging: The PCC adheres to Australian Standard AS/NZS 376.



## **Audio**

Concert PA - The paranaple convention centre has an L'Acoustic Kiva concert PA, consisting of LR main hangs, subs and infill

Control - Control is via a Midas Pro1 running a DL251 stage box with 40 inputs and 16 returns.

Foldback 8 X Nexo PS10's on 4 sends 14 X RCF Art310a's 2 X RCF powered subs Full mic kits, stands, cables, drop boxes etc.

# Lighting

Various lighting packages available upon request.

## A/V

124 of 500mm X 500mm of Liantronics LED panel Vision racks with 8 input vision mixer with scaler, presenter view output to stage

2 X Canon XA35 Hi-Def cameras with tripods

## **Outside Broadcast**

Full outside broadcast capability Livestreaming and hybrid meeting solutions

